

Appendix H – Self-Evaluation Results – Public Right of Way

Summary

This initial self-evaluation of pedestrian facilities yielded the following results:

- 13.65% of sidewalks met accessibility criteria
- 44.22% of curb ramps met accessibility criteria
- 52.46% of trails met accessibility criteria
- 100% of pedestrian crossings met accessibility criteria
- 0% of traffic control signals had push buttons that are accessible, or had the pedestrian indications on recall
- 0% of traffic control signals had APS

Detailed self-evaluation results:

Sidewalks: All sidewalks constructed prior to 2010 are deemed to be non-compliant because of wide joints. Some may meet the slope requirements but the use of the ½” round jointer was prevalent up until 2010. The City has a total of 30.73 miles of sidewalk, of which 3.69 miles are compliant.

Curb Ramps: All pedestrian curb ramps within the City were reviewed to determine if they are compliant. The City owns 848 total ramps; 375 ramps are compliant and 473 ramps are non-compliant.

Trails: The City reviewed all hard surface trails (asphalt and concrete) within the City. Of the 13.21 miles of trail, 6.93 miles are compliant. Excluded from the evaluation are all grass and earthen trails, as these would not meet the requirements of a safe and stable surface.

Pedestrian crossings: The City currently maintains 3 pedestrian crossings, which include push buttons and flashing signs. All 3 of the facilities are compliant.

Traffic control signals: The City owns and operates 1 traffic signal and it is noncompliant.

City of Grand Rapids
ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED17			Yes	Yes	Good	24	0.6	2.6	Yes	0.3	1.2	Compliant	
PED18	8	3.5	Yes	Yes	Good	28	0.3	1.1	No	1.2	0.2	Compliant	
PED1061			Yes	No	Good	5.5	0.6	4.2	No			Compliant	
PED113	6	2.5	No	No	Good	15	1.1	5.2				Non Compliant	No Dome
PED114	5	3	No	No	Good	15	0.5	5.3				Non Compliant	No Dome
PED115	4.5	3	No	No	Good	13.5	2	6.3				Non Compliant	No Dome
PED116	4	2	No	No	Good	8	0.7	5.7				Non Compliant	No Dome
PED118	0	0	Yes	No	Good	0	0	0				Compliant	
PED198	18	5	No	Yes	Good	82.5	0.3	4.1				Non Compliant	No Dome
PED199	6.5	5	Yes	Yes	Good	32.5	0.7	4.2				Compliant	
PED200	5.5	4	No	Yes	Good	22	1.4	4.4				Non Compliant	No Dome
PED201	4	5	No	Yes	Good	20	1.2	16.6				Non Compliant	Running Slope
PED202	4	5	No	Yes	Good	20	1.7	3.8				Non Compliant	No Dome
PED203	14	4	No	No	Good	56	1.9	5.4				Non Compliant	No Dome
PED204	5	4	No	Yes	Good	20	1	4.1				Non Compliant	No Dome
PED205	4	5	No	Yes	Good	20	2.9	13.2				Non Compliant	No Dome
PED206	4	5	No	Yes	Good	20	1	12.2				Non Compliant	Running Slope
PED207	0	0	Yes	Yes	Good	0	1	3	Yes	0.1	1.4	Compliant	
PED208	6	5	No	Yes	Good	30	1.4	3.8				Non Compliant	No Dome
PED279	3	1.5	No	No	Replace	4.5	1.1	5.6				Non Compliant	No Dome
PED280	4	5	No	Yes	Good	20	0.9	6.5				Non Compliant	No Dome
PED281	4	3	No	Yes	Fair	12	3.4	0.9				Non Compliant	Cross Slope
PED282	4	2	No	No	Replace	8	2	6.6				Non Compliant	No Dome
PED283	6	3	No	No	Replace	18	1	2				Non Compliant	No Dome
PED284	6	3	No	No	Good	18	0.4	5.8				Non Compliant	No Dome
PED285	5	5	No	Yes	Good	25	0.4	5.3				Non Compliant	No Dome
PED504	5.5	3	No	Yes	Good	16.5	0.8	6.4				Non Compliant	No Dome
PED505			No	No	Replace	1	0	0				Non Compliant	No Dome
PED506	7	4.5	No	Yes	Good	31.5	0.7	4.1				Non Compliant	No Dome
PED507			No	No	Replace	1	0	0				Non Compliant	No Dome
PED508	6.5	2	No	No	Good	13	0.6	2.9				Non Compliant	No Dome
PED509	6.5	2	No	No	Good	13	1.2	5.3				Non Compliant	No Dome
PED517	6.5	5	Yes	No	Good	32.5	0.9	4	No			Compliant	
PED518	6.5	5	Yes	No	Good	32.5	0.3	4	No			Compliant	
PED519	6	5	No	No	Good	30	0.1	5.7				Non Compliant	No Dome
PED520	7	3.5	No	No	Good	24.5	0.8	5				Non Compliant	No Dome
PED624	3.5	3	No	Yes	Good	10.5	0.5	7.8				Non Compliant	No Dome
PED625	3	4	No	Yes	Replace	12	1.4	10.8				Non Compliant	Running Slope
PED626	4	3	No	Yes	Fair	12	0.1	7.3				Non Compliant	No Dome
PED643			Yes	No	Replace	1	0.7	0.1	No			Compliant	
PED646	5.5	2.5	No	No	Replace	13.75	3.1	11.9				Non Compliant	No Dome
PED661	5	3	No	Yes	Good	15	0.1	4.4				Non Compliant	No Dome
PED662	5	2	No	Yes	Good	10	0.8	6.3				Non Compliant	No Dome
PED671	5	2.5	No	No	Fair	12.5	0.8	5.3				Non Compliant	No Dome
PED793	5	3.5	No	No	Replace	17.5	0	0				Non Compliant	No Dome
PED794	6	5	No	No	Replace	30	0	0				Non Compliant	No Dome
PED795	5	4	No	No	Replace	20	0	0				Non Compliant	No Dome
PED796	5	4.5	No	No	Replace	22.5	0	0				Non Compliant	No Dome
PED797			No	No	Replace	1	0	0				Non Compliant	No Dome
PED798			No	No	Replace	1	0	0				Non Compliant	No Dome
PED799			No	No	Replace	1	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0.5	4.3	Yes	0.6	1	Compliant	
PED1260	0	0	Yes	No	Good	0	1.1	5.1	No			Compliant	Slope of roadways cause issues
PED67			Yes	Yes	Good	30	1	2.9	No			Compliant	
PED5785			Yes	Yes	Good	0	0	3.8	No			Compliant	
PED5384			Yes	Yes	Good		0.3	2.4	Yes	0.1	0.3	Compliant	
PED5385			Yes	Yes	Good		0.6	2.7	Yes	0.9	0.8	Compliant	
PED5386			Yes	Yes	Good		0.6	5.1	Yes	7	1.6	Compliant	
PED5388			Yes	Yes	Good		1.1	4.2	Yes	0.9	0.2	Compliant	

City of Grand Rapids
 ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED5389			Yes				0.9	0.9	No			Compliant	
PED79			Yes	Yes	Good	20	0.9	4.3	No			Compliant	
PED80	4.5	2	No	Yes	Good	9	1.9	7.2	No			Non Compliant	No Dome
PED81	6	4	No	Yes	Good	24	1.9	2.6				Non Compliant	No Dome
PED82	5	5	No	Yes	Good	25	3.6	6.9				Non Compliant	Cross Slope
PED83	5	4.5	No	Yes	Good	22.5	0.2	8				Non Compliant	No Dome
PED84	9	5	Yes	Yes	Good	45	1.3	3.4				Compliant	
PED85	6	3	No	Yes	Fair	18	3.1	8.4				Non Compliant	
PED257	6	2.5	Yes	Yes	Good	25	0.3	4.5	Yes	0.4	0.5	Compliant	
PED258	4	6	No	Yes	Good	24	4.8	6.5				Non Compliant	Cross Slope
PED259	6	6	Yes	Yes	Good	5	0.7	6.7	Yes	0.2	0.5	Compliant	
PED260	4	6	No	Yes	Good	24	0.9	6.9				Non Compliant	No Dome
PED261	6	16	Yes	Yes	Good	4.5	1.5	4.7	Yes	1.8	1.2	Compliant	
PED262	5	5	No	No	Good	25	0.2	4				Non Compliant	No Dome
PED263	6	6	Yes	Yes	Good	4.5	0.1	5.7	Yes	1.6	1	Compliant	
PED6983	6	6.5	Yes	Yes	Good	4.5	0.1	4.2	Yes	1.1	0.9	Compliant	
PED6984	6	6	Yes	Yes	Good		1.4	5.1	Yes	0	1.2	Compliant	
PED6985	6	6	Yes	Yes	Good		1.6	8.1	Yes	1.7	1.9	Compliant	
PED6986	6	9	Yes	Yes	Good		1.1	8.3	Yes	0.5	1.5	Compliant	
PED7384	6	6.5	Yes	Yes	Good		1	0.3	Yes	1	0.5	Compliant	
PED7385	6	4.5	Yes	Yes	Good		1.2	0.8	No	1.2	0.8	Compliant	
PED7385	6	5.5	Yes	Yes	Good		2	3.1	No	1.1	1.7	Compliant	
PED710	6	6	No	No	Good		0.8	0.8	No	0.8	0.8	Compliant	
PED710	6	6.5	Yes	Yes	Good		0.7	2.9	Yes	0.9	0.7	Compliant	
PED710	6	5	Yes	Yes	Good		1	0.7	Yes	1.1	1.3	Compliant	
PED710	6	5	Yes	Yes	Good		0.9	2.9	Yes	0.2	3.1	Compliant	
PED710	5	6.5	Yes	Yes	Good		0.8	1.8	No			Compliant	
PED710	0	0	Yes	Yes	Good		1.9	3.1	No			Compliant	
PED710	6	5.5	Yes	Yes	Good		0.4	4.7	Yes	0.3	0.3	Compliant	
PED710	6	5	Yes	Yes	Good		0.6	3.4	Yes	0.1	0.5	Compliant	
PED710	8.5	9	Yes	Yes	Good		1	2.9	No			Compliant	
PED710	6.5	5	Yes	Yes	Good		0.3	3.7	No	0.7	0.5	Compliant	
PED710	6.5	5	Yes	Yes	Good	30	0.4	4.3	Yes	1.1	0.4	Compliant	
PED710	6	6	Yes	Yes	Good	36	0.5	2.5	Yes	0.4	2.5	Compliant	
PED710	6.5	5.5	Yes	Yes	Good		0.2	4.6	Yes	0.3	0.1	Compliant	
PED179	4.5	4.5	Yes	Yes	Good	20.25	0.9	1.9	Yes	0.3	1.2	Compliant	
PED181	6	5	No	Yes	Fair	30	0.1	8	Yes			Non Compliant	No Dome
PED182	6	5	Yes	Yes	Good	24	0.5	3.8	Yes	0.9	0.6	Compliant	
PED183	6	5	Yes	Yes	Good	30	0.9	1.5	No			Compliant	
PED184	17	5	No	Yes	Good	80	0.1	14.8				Non Compliant	Running Slope
PED1324			Yes	Yes	Fair	16	0.8	4.8	Yes	0.8	0.6	Compliant	
PED1323	7		Yes	No	Good		0.7	7.5	Yes	1.7	0.5	Non Compliant	Cross Slope
PED1312	9	3	No	Yes	Replace	27	0.3	4.1				Non Compliant	No Dome
PED1313	6	3	Yes	No	Good	18	1.4	3.7	Yes	1.3	0.7	Compliant	
PED1314	5	4	Yes	No	Good	20	0.2	4.7	Yes	1.2	0.6	Compliant	
PED1315	16	4	No	No	Good	62	0.9	3.8				Non Compliant	No Dome
PED1062	0	0	Yes	No	Good		2.8	4.7	No			Non Compliant	Cross Slope
PED1062	0	0	Yes	No	Good		1.1	2.2	No			Compliant	
PED1062	0	0	Yes	No	Good		0.5	3.3	No			Compliant	
PED1177	5	5	Yes	No	Good	25	4	3.5	No			Non Compliant	Road Cross Slope
PED1178	5	5	Yes	No	Good	25	6.2	7.9	No			Non Compliant	Cross Slope
PED1181	5	5	Yes	No	Good	25	0.4	5.1	Yes	1.8	0.1	Compliant	
PED1182	5	5	Yes	No	Good	25	1.9	3.8	Yes	1.6	0.8	Compliant	
PED1183	5	5	Yes	No	Good	25	0.5	6.4	Yes	0.4	1.5	Compliant	
PED1184			No	No	Replace	1	0	0				Non Compliant	
PED521	6	5	Yes	No	Good	30	1.4	2.9				Compliant	
PED522	6	5	Yes	No	Good	30	2	3.4				Compliant	
PED523	5	3.5	No	Yes	Good	17.5	1.4	7.7				Non Compliant	No Dome
PED527	6	5	Yes	No	Good	30	0.9	4.2				Compliant	
PED528	6	5	Yes	No	Good	30	0.4	4.6				Compliant	
PED529	6	5	Yes	No	Good	30	2.4	4	No			Non Compliant	Cross Slope
PED530	9	4	Yes	No	Good	36	1.5	2.8				Compliant	
PED531	10	3.5	Yes	No	Good	35	0.8	5.1	Yes	1.5	0.3	Compliant	

City of Grand Rapids
ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED532	5	4	Yes	No	Good	20	4.5	5.1	No			Non Compliant	Cross Slope
PED533	10	3	Yes	No	Good	30	0.3	2.4				Compliant	
PED534	10	3	Yes	No	Good	30	0.5	1.1				Compliant	
PED59	14	3.5	Yes	Yes	Good	70	0.9	2.2	No			Compliant	
PED60	3.5	5	Yes	Yes	Fair	12.25	1	1.9	No			Compliant	
PED61	5	1.5	No	No	Good	7.5	0.6	13.8	No			Non Compliant	Running Slope
PED62	17	4	Yes	Yes	Good	64	0.7	2.1	No			Compliant	
PED1666	9	10	Yes	No			1.5	4	Yes	1.5	0.9	Compliant	No landing
PED1664	6	6	Yes	No			1.6	5.2	No			Non Compliant	
PED1665	4	10	Yes	No			0.9	3.9	Yes	1.6	0.1	Compliant	
PED1659	10	9	Yes	No			0.3	4.8	Yes	1.3	0.6	Compliant	
PED1660	10	10	Yes	No			0.2	3.5	Yes	0.9	0	Compliant	
PED1661	10	6	Yes	No			0.8	6.2	No			Non Compliant	No landing
PED1662	10	10	Yes	No			2.3	6.6	No			Non Compliant	Cross Slope
PED1663	10.5	8	Yes	No			2.6	6.5	Yes	1.5	1.1	Non Compliant	Cross Slope
PED1657	10	6	Yes	No			0.4	4	Yes			Compliant	
PED1658	10	9	Yes	No	Good		1.1	3.3	Yes	1.1	0.1	Compliant	
PED73	6	10	Yes	Yes	Good		0.9	3.9	Yes	1.3	1.1	Compliant	
PED73	6	10	Yes	Yes	Good		0.3	3.7	Yes	0.4	0.5	Compliant	
PED1988	10	5	Yes	No			1	4.5	Yes	0.5	0.4	Compliant	
PED244	6	5	Yes	No	Good	30	1.9	8.1	Yes	2.2	0.2	Non Compliant	No Dome
PED245	4	4	No	Yes	Good	16	1.4	6.6	No			Non Compliant	Cross Slope
PED246	6	3	No	Yes	Good	18	2.1	5.6				Non Compliant	Cross Slope
PED247	5	6	No	No		15	1.3	3.1	Yes	1.5	0.5	Compliant	No Dome
PED22	12	4	Yes	Yes	Good	48	0.2	2.2	No			Compliant	
PED23	21+	4	Yes	Yes	Fair	72	1.9	4.5	No			Compliant	
PED25	13.5	3.5	Yes	Yes	Good	47.25	0.7	1.3	No			Compliant	
PED40			No	Yes	Good	22.5	1.2	2.7	No			Compliant	Compliant except no domes
PED87	4	2	No	No	Fair	8	0.3	8.3				Non Compliant	No Dome
PED88	3.5	2	No	No	Good	7	2.8	11.8				Non Compliant	
PED93	4	3	No	No	Good	12	1.1	7.9				Non Compliant	No Dome
PED94	5	4	No	No	Poor	5	2.1	4.1				Non Compliant	Cross Slope
PED95	4.5	3	No	No	Good	13.5	1.4	9.4				Non Compliant	Running Slope
PED97	6	2	No	No	Good	12	0.3	3.2				Non Compliant	No Dome
PED98	3.5	2.5	No	No	Fair	8.75	0.6	2.3				Non Compliant	No Dome
PED105	5.5	4	No	Yes	Good	22	1.5	7				Non Compliant	No Dome
PED106			No	No	Replace	1	0	0				Non Compliant	No Dome
PED107	4	2	No	Yes	Good	8	2.1	7.5				Non Compliant	Cross Slope
PED108	6	3.5	No	Yes	Good	21	0.5	9.4				Non Compliant	Running Slope
PED109			No	No	Replace	1	0	0				Non Compliant	Running Slope
PED131	4	2.5	No	No	Fair	10	1.9	8.6				Non Compliant	No Dome
PED132	3	2	No	No	Fair	6	1.5	6.7				Compliant	
PED133	8	6	Yes	Yes	Good	48	1.5	4				Compliant	
PED136	4	1.5	No	No	Good	6	2.2	5.5				Non Compliant	Cross Slope
PED140	6	3.5	No	No	Good	21	2	1.6				Non Compliant	No Dome
PED143	4.5	3	No	Yes	Fair	13.5	0.4	5.8				Non Compliant	No Dome
PED145	16	2.5	No	Yes	Good	38.75	3.5	5.2				Non Compliant	Cross Slope
PED146	21+	3.5	No	Yes	Good	63	1.1	2.9				Non Compliant	No Dome
PED147	6	3	No	Yes	Fair	18	0.2	5.5				Non Compliant	No Dome
PED148	6	4	No	Yes	Good	24	1.4	6.7				Non Compliant	No Dome
PED185	8	4	No	Yes	Good	32	1.5	5.6				Non Compliant	No Dome
PED186	6	4	Yes	Yes	Good	24	1.7	1.1	No			Compliant	
PED188	4	5	No	Yes	Good	20	1.7	6.3				Non Compliant	No Dome
PED189	4	5	No	Yes	Good	20	0.1	8.4				Non Compliant	Running Slope
PED190	4	5	No	Yes	Good	20	2.5	5				Non Compliant	Cross Slope
PED191	6.5	4	No	Yes	Good	26	2	2.2				Non Compliant	Running Slope
PED192	11	5	No	No	Good	55	1	2.1				Non Compliant	No Dome
PED193	16	5	No	Yes	Good	77.5	2.2	0.8				Non Compliant	Cross Slope
PED194	4.5	4	No	Yes	Good	18	1.1	16.8				Non Compliant	Running Slope
PED195	6	5	No	Yes	Good	30	2.3	9.2				Non Compliant	Running Slope
PED447			No	No	Replace	1	0	0				Non Compliant	
PED448	5	4	Yes	No	Good	20	6.9	5.7				Non Compliant	Cross Slope
PED449	5	4	Yes	No	Good	20	0.2	4.9				Compliant	

City of Grand Rapids
ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED450	6	4	Yes	No	Good	24	0.8	3.8	Yes	1.2	0.5	Compliant	
PED603	4	2.5	No	Yes	Good	10	1.4	7.3				Non Compliant	No Dome
PED604	3.5	2	No	Yes	Fair	7	1.1	8.6				Non Compliant	Running Slope
PED605	3	1.5	No	Yes	Good	4.5	1.5	6.8				Non Compliant	No Dome
PED606	3	1.5	No	Yes	Good	4.5	1	5.9				Non Compliant	No Dome
PED607	3	1.5	No	Yes	Good	4.5	2	7.8				Non Compliant	No Dome
PED608	3	1.5	No	Yes	Good	4.5	1.4	6.6				Non Compliant	No Dome
PED610	4	3	No	No	Replace	1	0	0				Non Compliant	Running Slope
PED613	4	3	No	Yes	Fair	12	1.5	10.3				Non Compliant	Running Slope
PED614	4	3	No	Yes	Good	12	1.6	7.3				Non Compliant	No Dome
PED615	4	3	No	Yes	Fair	12	2.2	6.9				Non Compliant	Cross Slope
PED616	3.5	3	No	Yes	Good	10.5	0.3	9.7				Non Compliant	Running Slope
PED77			Yes	Yes	Good	63	1	2.8	No	1.1	1.6	Compliant	
PED78			Yes	Yes	Good	40	0.6	2.9	Yes			Compliant	
PED110	3	1.5	No	No	Replace	4.5	2	0.9	Yes	0.2	1.7	Non Compliant	No Dome
PED111	8.5	5	Yes	Yes	Good	42.5	1	5.7	Yes			Compliant	
PED112	8.5	5	Yes	Yes	Good	42.5	1.6	4.2				Compliant	
PED196	6.5	6	Yes	Yes	Good	39	1.6	6.2	Yes	0.1	0.8	Compliant	
PED197	6.5	5	Yes	Yes	Good	32.5	1.9	8	Yes	1.5	1.9	Compliant	
PED264	6	16	Yes	Yes	Good	6	0.7	4.4	Yes	1.4	0.9	Compliant	
PED265	4	5	No	Yes	Good	20	3.7	4.5				Non Compliant	Cross Slope
PED266	5	6	No	Yes	Good	30	0.3	8.6				Non Compliant	Running Slope
PED267	6	21+	Yes	Yes	Good	16	0.9	3.9	Yes	1.1	1.2	Compliant	
PED268	6	5	No	Yes	Good	30	1.6	7				Non Compliant	No Dome
PED269	9	5	No	Yes	Good	45	1.2	3.8				Non Compliant	No Dome
PED287	5	5	Yes	Yes	Good	25	0.6	0.8	No			Compliant	
PED330	3.5	3	Yes	Yes	Good	10.5	1	0.8	No			Compliant	
PED357	5	3	No	No	Replace	15	0.5	12.4				Non Compliant	Running Slope
PED368	0	0	Yes	Yes	Good	0.3	0.3	2.9	Yes	0.6	1.3	Compliant	
PED535	10	3	Yes	No	Good	30	1.8	1				Compliant	
PED536	10	3	Yes	No	Good	30	0.4	3.1	No			Compliant	
PED537	10	3	No	No	Replace	1	0	0				Non Compliant	
PED538	5	5	Yes	No	Good	25	1.4	3.4	No			Compliant	
PED539	4	5	Yes	No	Good	20	1	7	Yes	0.8	1.8	Compliant	
PED540	4.5	4	Yes	No	Good	18	0.8	4.3				Compliant	
PED550	4	5	Yes	No	Good	20	1.1	4	No			Compliant	Cross Slope
PED552	5	4	No	Yes	Good	20	5.5	7				Non Compliant	Cross Slope
PED553	5	4	No	Yes	Good	20	2.5	4				Non Compliant	Cross Slope
PED554	5	4	No	Yes	Replace	20	1.9	8.8				Non Compliant	Running Slope
PED555	5	4	No	Yes	Replace	20	1.2	8.7				Non Compliant	Running Slope
PED556	5	5	No	Yes	Good	25	1.1	9.2				Non Compliant	Running Slope
PED557	5	4	No	Yes	Good	20	0.3	9.9				Non Compliant	Running Slope
PED590	6	3	No	Yes	Good	18	0	6.4				Non Compliant	No Dome
PED591	3	2	No	Yes	Good	6	1.5	8.9				Non Compliant	Running Slope
PED592	0	0	No	No	Replace	1	0	0				Non Compliant	
PED593	4	2.5	No	Yes	Good	10	3	9.9				Non Compliant	
PED594	3.5	1.5	No	Yes	Good	5.25	0.4	8.6				Non Compliant	Running Slope
PED595	3	2	No	Yes	Good	6	0.9	7.6				Non Compliant	No Dome
PED596	3	1.5	No	Yes	Good	4.5	0.4	8.7				Non Compliant	Running Slope
PED597	5	5	Yes	No	Good	25	2.3	2.2	Yes	1.4	1.6	Non Compliant	Cross Slope
PED599	5	4	Yes	No	Good	20	0.1	4.9				Compliant	
PED600	4	3	Yes	No	Good	12	1.9	4.8	No			Compliant	
PED602			No	No	Replace	1	0	0				Non Compliant	
PED619	4	3	No	Yes	Good	12	0.8	7.4				Non Compliant	No Dome
PED620	4	3	No	Yes	Good	12	1.2	13				Non Compliant	Running Slope
PED621	4	3	No	Yes	Good	12	1.2	11				Non Compliant	Running Slope
PED622	3	3	No	Yes	Fair	9	0.5	10.3				Non Compliant	Running Slope
PED623	4	3	No	Yes	Good	12	1	11.3				Non Compliant	Running Slope
PED617	4	3	No	Yes	Fair	12	0.4	9.4				Non Compliant	Running Slope
PED618	4	3	No	Yes	Good	12	1.2	10.6				Non Compliant	Running Slope
PED672	5	2	No	Yes	Good	10	0.9	2.9				Non Compliant	No Dome
PED673	4	2.5	No	No	Good	10	0.7	5.1				Non Compliant	No Dome
PED674	4	2.5	No	No	Fair	10	0.6	7.2				Non Compliant	No Dome

City of Grand Rapids
 ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED675	4.5	3	No	No	Fair	13.5	2.4	16.6				Non Compliant	
PED676	6	No	No	No	Good	6	0.3	80				Non Compliant	Running Slope
PED690	8.5	5	Yes	Yes	Good	42.5	0.7	5.4	Yes	1.9	0.1	Compliant	
PED691	8	5	Yes	Yes	Good	40	0.9	5.6	Yes	2	1	Compliant	
PED694	8	6	Yes	Yes	Good	48	1	3.2				Compliant	
PED695	6.5	4	No	No	Good	26	0.5	9.6				Non Compliant	Running Slope
PED696	5	3	No	Yes	Good	15	0.4	11				Non Compliant	Running Slope
PED697	6	5	No	Yes	Fair	30	1.3	8.1				Non Compliant	No Dome
PED698	0	0	Yes	Good	Good	0	0.1	4.1	Yes	0.3	0.8	Compliant	
PED809	7	3	No	No	Good	21	1.2	6.3				Non Compliant	No Dome
PED810	6	1.5	No	No	Good	9	1.7	4.3				Non Compliant	No Dome
PED800			No	No	Replace	1	0	0				Non Compliant	
PED801			No	No	Replace	1	0	0				Non Compliant	
PED802			No	No	Replace	1	0	0				Non Compliant	
PED803	10	3	No	Yes	Good	30	2.8	6.3				Non Compliant	Cross Slope
PED804	5.5	3.5	No	Yes	Good	19.25	2.6	8				Non Compliant	Cross Slope
PED805	5	3	No	Yes	Good	15	3.2	8.8				Non Compliant	
PED806	6	3	No	No	Good	18	5	9.7				Non Compliant	
PED807	4	2.5	No	No	Good	10	0.5	9.4				Non Compliant	Running Slope
PED808	5.5	2	No	No	Fair	11	2.8	4.9	Yes	0.9	1.2	Compliant	Cross Slope
PED910	5.5	5	Yes	Yes	Good	1	0.7	1.3				Compliant	
PED913	11		No	Yes	Good	11	0.7	3.5				Non Compliant	No Dome
PED931	5	4	No	Yes	Good	20	1.8	7.9				Non Compliant	No Dome
PED934	5	4	No	Yes	Good	20	1.4	7.9				Non Compliant	No Dome
PED936	5	4	No	Yes	Good	20	2.5	9.4				Non Compliant	Cross Slope
PED937	4.5	5	Yes	Yes	Good	22.5	2.1	7.2				Non Compliant	Cross Slope
PED939	4	5	Yes	No	Good	20	0.8	7.9	Yes	0.3	0.1	Compliant	
PED941	5	3	No	Yes	Good	15	2.7	7.7				Non Compliant	Cross Slope
PED942	5	4	No	Yes	Good	20	1.6	6.7				Non Compliant	No Dome
PED992	7.5	3	No	No	Replace	22.5	0.5	3.9				Non Compliant	No Dome
PED993	3.5	2	No	No	Fair	7	1.1	6.9				Non Compliant	No Dome
PED994	5	4	No	Yes	Good	20	0.6	6.3				Non Compliant	No Dome
PED995	5.5	2.5	No	Yes	Fair	13.75	0.6	10.4				Non Compliant	Running Slope
PED996	5	2	No	No	Replace	10	3.9	9.2				Non Compliant	
PED997	6	2	No	No	Replace	12	0.4	8.4				Non Compliant	Running Slope
PED998	7	2	No	No	Good	14	0.5	8.5				Non Compliant	Running Slope
PED999	5	2	No	No	Replace	10	0	0				Non Compliant	
PED1000	6.5	2.5	No	Yes	Fair	16.25	0.7	7.8				Non Compliant	No Dome
PED1001			No	No	Replace	1	0	0				Non Compliant	No Dome
PED1046	3.5	3	No	Yes	Good	10.5	0.4	8.1				Non Compliant	No Dome
PED1047	3.5	3	No	Yes	Replace	10.5	1.7	1.2				Non Compliant	No Dome
PED1048	3.5	3	No	Yes	Good	10.5	0.6	7.9				Non Compliant	No Dome
PED1049	3	3	No	Yes	Good	9	0	8.3				Non Compliant	No Dome
PED1050			No	No	Replace	1	0	0				Non Compliant	No Dome
PED1052	3	3	No	Yes	Good	9	4.5	10.1				Non Compliant	Running Slope
PED1080	5	2	No	Yes	Good	10	1	9.4				Non Compliant	No Dome
PED1081	5	4	No	Yes	Good	20	0.2	7.6				Non Compliant	No Dome
PED1103	3	1.5	No	Yes	Good	4.5	0.4	8.1				Non Compliant	No Dome
PED1105			No	No	Replace	1	0	0				Non Compliant	
PED1106			No	No	Replace	1	0	0				Non Compliant	
PED1242	4	5	Yes	No	Good	20	1	4.7	No			Compliant	
PED1245	4	5	Yes	No	Good	20	2.2	4.3	No			Non Compliant	Cross Slope
PED1303	4	5	Yes	No	Good	20	1.1	4.2	Yes	0.5	1.3	Compliant	
PED1304	4	5	Yes	No	Good	20	1.2	4.7				Compliant	
PED1305	4	6	Yes	Yes	Good	24	3.5	5.2	Yes	1.3	0.3	Non Compliant	Cross Slope
PED1306	8.5		No	No	Replace	8.5	0	0				Non Compliant	
PED1307			No	No	Replace	1	0	0				Non Compliant	
PED1308	6	6.5	No	No		20	1.5	0.1	No			Compliant	No Dome
PED1309	6	7	No	No		20	0.8	5	No			Conditionally Compliant	Street Grade too steep for landing
PED1310	6	4	No	No	Good	24	0.6	1.1	No			Compliant	Cross Slope
PED1311	6	6.5	No	No	Good	24	0.7	5.2	No			Conditionally Compliant	Street Grade too steep for landing
PED730	4	3	No	No	Good	12	0.7	8				Non Compliant	No Dome
PED731	4.5	3.5	No	No	Fair	15.75	3.1	10.1				Non Compliant	

City of Grand Rapids
ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED788	6	5	No	No	Replace	30	0	0				Non Compliant	
PED789	5	6	No	No	Replace	30	0	0				Non Compliant	
PED790	5.5	4	No	No	Replace	22	0	0				Non Compliant	
PED791	6	5	No	No	Replace	30	0	0				Non Compliant	
PED792	5	3.5	No	No	Replace	17.5	0	0				Non Compliant	
PED1126	13.5	5	Yes	No	Good	67.5	1.7	3.8	No			Compliant	
PED1252	8.5	3	Yes	No	Good	25.5	0.4	0.1				Compliant	
PED1253	9	4	Yes	No	Good	36	1.3	4.3				Compliant	
PED1254			No	No	Replace	1	0	0				Non Compliant	
PED1256	4	1.5	No	No	Fair	6	1.6	10				Non Compliant	Running Slope
PED1257			No	No	Replace	1	0	0				Non Compliant	
PED1258			No	No	Replace	1	0	0				Non Compliant	
PED1259			No	No	Replace	1	0	0				Non Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1261	9	4.5	Yes	No	Good	40.5	4.9	6.6	Yes	1.7	1.6	Non Compliant	Cross Slope
PED1262	9	4.5	Yes	No	Good	40.5	3.5	6.2	No			Non Compliant	Cross Slope
PED1263	9	3	Yes	No	Good	27	0.7	3				Compliant	
PED1264	8.5		No	No	Replace	8.5	0	0				Non Compliant	
PED1265	8	5	Yes	No	Good	40	0.5	3				Compliant	
PED1278	16	4	No	Yes	Good	62	2	4.1				Non Compliant	No Dome
PED1279	5	3	Yes	No	Good	15	0.1	1.6				Compliant	
PED1280	5	3	Yes	No	Good	15	1	4.4				Compliant	
PED1281	5	3	Yes	No	Good	15	0.4	4.2				Compliant	
PED1282	5	3	Yes	No	Good	15	1	2.5				Compliant	
PED1283	8	2	No	Yes	Fair	16	2.3	4.3	Yes	1.2	0.2	Non Compliant	Cross Slope
PED1284	10	2.5	No	Yes	Good	25	5.9	7.6				Non Compliant	Cross Slope
PED1287	3	3	No	Yes	Good	9	0.2	7.9				Non Compliant	No Dome
PED1298	3.5	3	No	Yes	Good	10.5	0.8	7.6				Non Compliant	No Dome
PED1299	6	4	No	Yes	Good	24	1.5	8.5				Non Compliant	Running Slope
PED1300	6	4	No	Yes	Good	24	2.4	9.8				Non Compliant	
PED1302	5	4	No	Yes	Good	20	3.1	7				Non Compliant	Cross Slope
PED1639	8.5	5	Yes	No	Good	42.5	1.3	1.8	Yes	1.3	1.8	Compliant	
PED157	6	4	Yes	Yes	Good	24	1.3	8.1	Yes	1.2	1.6	Compliant	
PED158	5.5	3	No	Yes	Good	16.5	0.3	8.3				Compliant	
PED159	5.5	3	No	Yes	Poor	5.5	0.7	7.1				Compliant	No Dome
PED160	12	3	No	Yes	Good	36	3.7	6.4				Non Compliant	No Dome
PED162	6	2	No	Yes	Good	12	0.4	5.4				Non Compliant	Cross Slope
PED163	6	4	No	Yes	Fair	24	1	3.7				Non Compliant	No Dome
PED164	6	2	Yes	Yes	Good	12	1.3	3.7	Yes	0.4	0.6	Compliant	
PED165	6.5	5	No	Yes	Good	32.5	2.5	6.3				Non Compliant	Cross Slope
PED166	8	2	No	No	Good	16	2	4.5				Non Compliant	No Dome
PED167	6	5	Yes	Yes	Good	28.5	1.9	5.7	Yes	1.9	1.7	Conditionally Compliant	
PED168	5	3	No	Yes	Good	15	1.1	11.1				Non Compliant	Running Slope
PED254	5	5	No	Yes	Good	25	0.1	5.5				Non Compliant	No Dome
PED255	6	18	Yes	Yes	Good	20	1.3	5.3	Yes	0.9	1.8	Compliant	
PED256	5	5	No	Yes	Good	25	0.8	8.2				Non Compliant	No Dome
PED270	5	5	No	Yes	Good	25	1.8	9.3				Non Compliant	Running Slope
PED271	5	6	No	Yes	Good	30	2	5.8				Non Compliant	No Dome
PED272	5	6	No	Yes	Good	30	2	7				Non Compliant	No Dome
PED274	4.5	4.5	No	Yes	Poor	20.25	0.3	4.7				Non Compliant	No Dome
PED275	4	5	No	Yes	Good	20	0.9	7.8				Non Compliant	No Dome
PED276	3	3	No	No	Replace	9	2.1	8.2				Non Compliant	Cross Slope
PED277	4	3	No	No	Good	12	0.1	7.4				Non Compliant	No Dome
PED278	4	5	No	Yes	Good	20	2.5	6.1				Non Compliant	Cross Slope
PED318	7	2.5	No	Yes	Fair	17.5	1.1	7.5				Non Compliant	No Dome
PED319	4	2	No	Yes	Fair	8	1.1	8.4				Non Compliant	Running Slope
PED320	5.5	2	No	No	Fair	11	0.6	5.1				Non Compliant	No Dome
PED321	5	2	No	No	Replace	10	1.5	10.9				Non Compliant	Running Slope
PED322	3	2	No	No	Fair	6	3.8	11.5				Non Compliant	
PED323			No	No	Replace	1	0	0				Non Compliant	No Dome
PED324	5.5	2	No	Yes	Good	11	1.4	5.8				Non Compliant	No Dome
PED325	0		No	No	Replace	1	0	0				Non Compliant	
PED326			No	No	Replace	1	0	0				Non Compliant	

City of Grand Rapids
ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED327	6	5	Yes	Yes	Good	30	0.3	1.2	No			Compliant	
PED328	5.5	9	Yes	Yes	Good	1	0.3	3	Yes	0.6	0.8	Compliant	
PED329	5	5	Yes	Yes	Good	1	1.1	5	Yes	0.5	1	Compliant	
PED558	6	4	No	Yes	Good	24	4.3	10.9				Non Compliant	
PED559	6	4	No	Yes	Good	24	6.2	9.3				Non Compliant	
PED560	6	5	No	Yes	Good	30	3.5	6.8				Non Compliant	Cross Slope
PED561	6	5	No	Yes	Good	30	1.2	7.1				Non Compliant	No Dome
PED562	6	4	No	Yes	Good	24	0.5	7.6				Non Compliant	No Dome
PED563	6	5	No	Yes	Good	30	0.8	7.8				Non Compliant	No Dome
PED564	10	5	No	Yes	Good	50	0.2	3.8				Non Compliant	No Dome
PED565	16	5	No	Yes	Good	77.5	2.4	2.4				Non Compliant	Cross Slope
PED677	5	1.5	No	No	Good	7.5	1	6.2				Non Compliant	No Dome
PED678	6	1.5	No	No	Good	9	1.2	6.6				Non Compliant	No Dome
PED679			No	No	Replace	1	0	0				Non Compliant	No Dome
PED680	5	1.5	No	No	Good	5	0.5	10.6				Non Compliant	Running Slope
PED681	5.5	1.5	No	No	Good	8.25	1.1	8.4				Non Compliant	Running Slope
PED682	4	2	Yes	Yes	Fair	8	1	0.5	No			Compliant	
PED683	4	2.5	No	No	Fair	10	0.3	7.2				Non Compliant	No Dome
PED684	4	2	No	No	Good	8	0.7	11.2				Non Compliant	Running Slope
PED685	4	2	No	No	Good	8	0.1	11.3				Non Compliant	Running Slope
PED686	5	3	No	Yes	Good	15	0.1	7.8				Non Compliant	No Dome
PED687	6	3	No	No	Good	18	0.1	10.8				Non Compliant	Running Slope
PED710	7	8	Yes	Yes	Good	28	0.8	3	Yes	0.8	1.9	Compliant	
PED711	7	4	No	Yes	Good	28	0.4	6.3				Non Compliant	No Dome
PED712	5	3	Yes	Yes	Good	15	0.9	3.2	Yes	0.2	0.5	Compliant	
PED713	4.5	3	Yes	No	Fair	13.5	0.5	4.3	Yes	0.6		Compliant	
PED716	7	4	No	Yes	Fair	28	0.3	4.3				Non Compliant	No Dome
PED717	6	5	No	No	Good	30	0.2	3.9				Non Compliant	No Dome
PED916	5	4	No	Yes	Good	20	3.9	9				Non Compliant	Cross Slope
PED917	8	2	No	Yes	Good	16	2.5	6.8				Non Compliant	
PED919	5	4	No	Yes	Good	20	1.4	7.6				Non Compliant	No Dome
PED922	5	4	No	Yes	Good	20	0.3	10.3				Non Compliant	Running Slope
PED923	4	3.5	No	Yes	Good	14	1.1	8.1				Non Compliant	No Dome
PED926	5	4	No	Yes	Good	20	0.7	7.6				Non Compliant	No Dome
PED927	6	4	No	Yes	Good	24	3.4	7.5				Non Compliant	Cross Slope
PED928	5	4	No	Yes	Good	20	2.4	6.7				Non Compliant	Cross Slope
PED929	5	4	No	Yes	Good	20	0.9	10.4				Non Compliant	Running Slope
PED930	3	2	No	Yes	Good	6	3.7	7.3				Non Compliant	Cross Slope
PED962	4.5	3	No	Yes	Good	13.5	0.9	7.3				Non Compliant	No Dome
PED984	3	3	No	No	Poor	9	4.4	10.3				Non Compliant	Cross Slope
PED985	7	3	No	No	Fair	21	3.1	7.1				Non Compliant	
PED986	15	5	No	No	Good	75	2.8	23.1				Non Compliant	
PED987	5	2	No	No	Fair	10	1.4	15.7				Non Compliant	Running Slope
PED988	6	1.5	No	No	Fair	9	2.6	5.7				Non Compliant	Cross Slope
PED989	3	3	No	No	Good	9	1.2	14.4				Non Compliant	Running Slope
PED990	6	3	No	No	Fair	18	4	5.3				Non Compliant	Cross Slope
PED991	5	2	No	No	Replace	10	7	0.8				Non Compliant	Cross Slope
PED1002			No	No	Replace	1	0	0				Non Compliant	
PED1004	3.5	3.5	No	Yes	Good	12.25	2.3	9.2				Non Compliant	No Dome
PED1005	3.5	3.5	No	Yes	Good	12.25	0.5	7.7				Non Compliant	No Dome
PED1006	4	3	No	Yes	Good	12	0.5	12.9				Non Compliant	Running Slope
PED1007	7	3	No	Yes	Good	21	0.1	5				Non Compliant	No Dome
PED1008	4	3	No	Yes	Good	12	3.4	8.5				Non Compliant	Running Slope
PED1009	4	3	No	No	Replace	12	1.1	10.3				Non Compliant	No Dome
PED1010	5	3	No	Yes	Fair	25	1.5	7				Non Compliant	Running Slope
PED1011	4	3	No	Yes	Good	12	0.3	8.7				Non Compliant	Running Slope
PED1012	5	2	No	No	Good	10	2.3	7.7				Non Compliant	Cross Slope
PED1013	9	4	No	No	Good	9	0.7	7.6				Non Compliant	No Dome
PED1014	4	3.5	No	Yes	Fair	14	2.2	7.8				Non Compliant	Cross Slope
PED1025	3	3	No	Yes	Good	9	4	11.1				Non Compliant	
PED1026			No	No	Replace	1	0	0				Non Compliant	
PED1027			No	No	Replace	1	0	0				Non Compliant	
PED1082	5	4	No	Yes	Good	20	0.5	8				Non Compliant	No Dome

City of Grand Rapids
 ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED1083	6	3	No	Yes	Good	18	0	9				Non Compliant	Running Slope
PED1084	4	3	No	No	Good	6	0.5	2.2				Non Compliant	No Dome
PED1086	4	3	No	No	Replace	12	1.6	8.6				Non Compliant	Running Slope
PED1088	5	4	No	Yes	Good	20	1.8	9.9				Non Compliant	Running Slope
PED1089	5	4	No	Yes	Good	20	0.3	10.6				Non Compliant	Running Slope
PED1090	5	3.5	No	No	Good	17.5	0.7	7.8				Non Compliant	No Dome
PED1091	4.5	4	No	Yes	Good	18	2.1	3.5				Non Compliant	Cross Slope
PED1099	3	2	No	No	Replace	1	0.2	0				Non Compliant	No Dome
PED1100	3	2	No	Yes	Good	6	1.5	7.4				Non Compliant	No Dome
PED1101	3	1.5	No	Yes	Good	4.5	1.7	8.8				Non Compliant	Running Slope
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	Running Slope
PED1260	0	0	Yes	No	Good	0	1.3	4.2	Yes	1.4	1.1	Compliant	Running Slope
PED1649	6	6	Yes	No			1	4	No			Compliant	
PED1650			Yes	No			0.9	3.8	No			Compliant	
PED1250	8	5	Yes	No	Good	40	0.5	4.1				Compliant	
PED1251	4	6	Yes	No	Good	24	0.4	4	No			Compliant	
PED1249	8	5	Yes	No	Good	40	2.6	2.1	No			Non Compliant	Cross Slope
PED1194	6	5	Yes	No	Good	30	1.1	5.2	Yes	2	0.7	Compliant	Running Slope
PED1196	4	4	Yes	No	Good	16	0.6	3.9				Compliant	
PED1197			No	No	Replace	1	0	0				Non Compliant	
PED1214	8	4	No	Yes	Good	32	7.4	11.4				Non Compliant	Cross Slope
PED1215	8	4	No	Yes	Good	32	5	8.8	No			Non Compliant	Cross Slope
PED1216	7	4	No	Yes	Good	28	2	11.9				Non Compliant	Running Slope
PED1232	14	3	Yes	No	Good	42	4.5	2.4				Non Compliant	Cross Slope
PED1236	5	5	Yes	No	Good	25	3.6	2.9				Non Compliant	Cross Slope
PED1237			No	No	Replace	1	0	0				Non Compliant	
PED1238			No	No	Replace	1	0	0				Non Compliant	
PED1190	5	5	Yes	No	Good	25	2.4	4.7	No			Non Compliant	Cross Slope
PED1191	4	3	Yes	No	Good	12	2.2	3	No			Non Compliant	Cross Slope
PED1271	8	5	Yes	No	Good	40	1.5	3.2				Compliant	Cross Slope
PED1272	8	5	Yes	No	Good	40	1.4	2.6	No			Compliant	Cross Slope
PED1273	5	5	No	Yes	Good	25	2.6	12.8				Non Compliant	Running Slope
PED1274	6	5	No	Yes	Good	30	1.1	10.3				Non Compliant	Running Slope
PED1275	6	5	No	Yes	Good	30	1.9	10.8				Non Compliant	Running Slope
PED1276	6	4	No	Yes	Good	24	3.2	7				Non Compliant	Running Slope
PED1277	8	5	Yes	No	Good	40	1.4	4.1				Compliant	Cross Slope
PED541	4	5	Yes	No	Good	20	0.7	2.3	No			Compliant	Cross Slope
PED544	5	5	No	Yes	Good	25	0.4	11.6				Non Compliant	Running Slope
PED545	12	5	No	Yes	Good	60	3.3	5.2				Non Compliant	Cross Slope
PED546	12	5	No	Yes	Good	60	1.8	4.6				Non Compliant	No Dome
PED547	6	4	No	Yes	Good	24	0.8	7.3				Non Compliant	No Dome
PED548	4	5	Yes	No	Good	20	0.7	4.8				Compliant	
PED549	4	5	Yes	No	Good	20	0.2	3	No			Compliant	
PED1127	5	5	Yes	No	Good	25	1.6	4.3	No			Compliant	
PED1128	4	5	Yes	No	Good	20	0.3	4.6	No			Compliant	
PED1130			No	No	Replace	1	0	0				Non Compliant	Cross Slope
PED1172	5	5	No	No	Good	25	4.5	6				Non Compliant	
PED1173	5	5	Yes	No	Good	25	1.2	3.2	No			Compliant	
PED1174	5	5	Yes	No	Good	25	1	3.7				Compliant	
PED1175	5	5	Yes	No	Good	25	1.2	7.6	Yes	2	0.8	Compliant	
PED1176			No	No	Replace	1	0	0				Non Compliant	
PED1246	4	5	Yes	No	Good	20	1	4.8	No			Compliant	
PED1247	8	5	Yes	No	Good	40	0.3	4.4				Compliant	
PED1248	8	5	Yes	No	Good	40	1.9	4.6	Yes	0.7	0.2	Compliant	
PED1651	6	6	Yes	No	Good	36	0.7	5.9	Yes	0.7	1.5	Compliant	
PED1653			Yes	No			1.9	4.3	No			Compliant	
PED1654			Yes	No			1.8	4.8	No			Compliant	
PED1655	10	5	Yes	No			0.4	2.9	Yes	1.6	0.4	Compliant	
PED1656	10	5	Yes	No	Good	20	0.1	5.2	No			Non Compliant	Slope too great and no landing
PED1192	4	5	Yes	No	Good	20	2	4.9	No			Compliant	Directional would be better
PED1193	6	6	Yes	No	Good	36	1.6	4.7	No			Compliant	
PED1229	21+	4	Yes	No	Good	72	0.1	4	No			Compliant	Directional would be better

City of Grand Rapids
ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED1230	16	3	Yes	No	Replace	46.5	3.2	1.7	No			Non Compliant	Cross slope not compliant due to road slope
PED1231	13	3	Yes	No	Good	39	2.3	2.4	No			Non Compliant	Cross slope not compliant due to road slope
PED73	0	0	Yes	Yes	Good		0.3	1.7	Yes	0.3	1.3	Compliant	
PED73	0	0	Yes	Yes	Good		0.9	2	Yes	1.5	0.1	Compliant	
PED73	0	0	Yes	Yes	Good		0.7	2	Yes	0.6	0	Compliant	
PED73	0	0	Yes	Yes	Good		0.7	3	No			Compliant	
PED73	0	0	Yes	Yes	Good		0.5	3.7	Yes	0.7	1.3	Compliant	
PED73	0	0	Yes	Yes	Good		0.4	4.2	Yes	0.7	0.6	Compliant	
PED73	6	6	Yes	Yes	Good		0.3	3.5	Yes	0.6	0.8	Compliant	
PED4583			Yes	Yes	Good		0.3	1.7	No			Compliant	
PED4983			Yes	Yes	Good		0.9	1.5	Yes	0.7	0.8	Compliant	
PED4183			Yes				0	3	No			Compliant	
PED4184			Yes				0.8	3.6	No			Compliant	
PED4985			Yes				0.2	3.5	Yes	0.3	0.4	Compliant	
PED4986			Yes				1	2.5	Yes	1.3	0.1	Compliant	
PED4984			Yes				1.2	4.9	Yes	1.3	0.8	Compliant	
PED331	8	1.5	No	No	Good	12	0.5	4.5	Yes	0.4	1.5	Compliant	No Dome
PED332	3	3	Yes	No	Good	9	0.6	5	Yes	0.1	0.4	Compliant	
PED333	3	3	Yes	No	Good	9	0	1	Yes	0.1	0.4	Compliant	
PED334	4	0	No	No	Fair	4	0.5	8.2	Yes	0.5	1	Compliant	No Dome
PED335	0	0	Yes	Yes	Good		0.2	2	Yes			Compliant	
PED295	4	3	Yes	Yes	Good	12	0.5	2.6	Yes	1	1.6	Compliant	
PED298	4	3	Yes	No	Good	12	1.2	2.8	Yes	0.7	1.3	Compliant	
PED299	0	0	Yes	Yes	Good		1.3	3.8	Yes	1.4	1.1	Compliant	
PED288	5	5	Yes	Yes	Good	25	1	0.6	No			Non Compliant	
PED289	6	4	Yes	Yes	Good	24	2.1	0.7	No			Non Compliant	Cross Slope
PED294	6	6	Yes	Yes	Good	36	0.4	1.8	No			Compliant	
PED4989			Yes				0.2	1	No			Compliant	
PED5383			Yes				0.8	0.4	No			Compliant	
PED63	6	6	Yes	No	Fair	18	1	2.4	Yes	1.2	0.6	Compliant	
PED64	5.5	3	No	No	Fair	16.5	0.5	5.1				Non Compliant	No Dome
PED65	5.5	3.5	No	No	Fair	19.25	3.1	8.1				Non Compliant	Cross Slope
PED26			Yes	No	Good	18	1.5	0.9	No			Compliant	
PED4186			Yes				0.4	0.4	No			Compliant	
PED826	6	4	Yes	No	Good	24	3	5.7	Yes	0.7	0.6	Non Compliant	Cross slope not compliant due to road slope
PED827	6	4	Yes	No	Good	24	2.4	4.3	No			Non Compliant	Cross slope not compliant due to road slope
PED828	6	5	Yes	No	Good	30	0.9	3.8	No			Compliant	
PED829	6	3	Yes	No	Good	18	0.3	2	No			Compliant	
PED4987			Yes				0.8	1.2	No			Compliant	
PED1062	0	0	Yes	No	Good		1.4	5	Yes	0.6	1	Compliant	
PED73	6	5	Yes	Yes	Good		0.6	3.1	Yes	0.4	1.1	Compliant	
PED73	6	5	Yes	Yes	Good		1.9	2.9	Yes	1.4	1	Compliant	
PED368	0	0	Yes		Good		0.8	2.4	Yes	1.1	0.9	Compliant	
PED368	0	0	Yes		Good		0.9	2.4	Yes	1	0.9	Compliant	
PED3783			Yes				1	0.7	No			Compliant	
PED3784			Yes				0.3	4.3	Yes	0.6	0.8	Compliant	
PED75	5.5	10	Yes	Yes	Good	11	0.9	2.7	Yes	0.2	1.9	Compliant	
PED76	6	6	Yes	Yes	Good	22.75	1.1	2.8	Yes	1.7	0.3	Compliant	
PED41			Yes	Yes	Good	24	1.3	5	Yes	1	0.9	Compliant	
PED44	5.5	4	No	Yes	Good	22	4.2	5.4	Yes	0.8	0.8	Non Compliant	Cross Slope
PED5788			Yes				0.5	1.7	Yes	0.9	0.2	Compliant	
PED1322	4		Yes	No	Good		1.5	5.2	Yes	1.7	1.8	Compliant	
PED5392			Yes				1.1	4	Yes		1	Compliant	
PED1063			Yes	No	Replace	1	0.6	1.6	No			Compliant	
PED455	6	4	No	Yes	Good	24	1.6	8.3				Non Compliant	No Dome
PED456	7	4	No	Yes	Good	28	1.7	7.3				Non Compliant	No Dome
PED457	5	3	No	No	Good	15	0.2	8.6				Non Compliant	Running Slope
PED458	5	3	No	Yes	Poor	15	0.4	7.8				Non Compliant	No Dome
PED5791			Yes	Yes	Good		0.8	5.7	Yes	0.8	0.8	Compliant	Landing is further up the slope
PED6184	6.5	8.5	Yes	Yes	Good		1.3	1.9	Yes	1.3	1	Compliant	
	6.5	4	Yes	Yes	Good		1.5	7.4	Yes	0.8	1.2	Compliant	
	6.5	4	Yes	Yes	Good		1.5	7.1	Yes	1.2	0.8	Compliant	

City of Grand Rapids
ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED66	8		Yes	Yes	Good	32	1	2.1	No			Compliant	
PED29	4.5	4	Yes	No	Fair	18	1.2	1.3	No			Compliant	
PED30			Yes	Yes	Good	25	0.3	1.3	No			Compliant	
PED5786												Compliant	
PED5787			Yes				0.4	3.3	Yes	0.5	1	Compliant	
PED5387			Yes				1.2	3.2	No			Compliant	
PED5390			Yes				1.4	4.4	Yes	1.6	1.1	Compliant	
PED5391			Yes				0.6	4.4	Yes	1.1	0	Compliant	
PED70			Yes	Yes	Good	68	0.4	4.2	Yes	0.3	0.8	Compliant	
PED73	0	0	Yes	Yes	Good	77	0.6	4.1	Yes	1	1.3	Compliant	
PED74			Yes	Yes	Good	22	0.1	4.1	Yes	0.4	0.2	Compliant	
PED1316	4	4	No	Yes	Good	16	0.4	8.6		0.3	0.6	Compliant	
PED1317	5	4	No	Yes	Good	20	1.3	8.4				Non Compliant	Running Slope
PED1318	5	4	No	Yes	Good	20	2.3	5.2				Non Compliant	Running Slope
PED1319	5	4	No	Yes	Good	20	2.3	5.2				Non Compliant	Cross Slope
PED1320	5	4	No	Yes	Good	16	1.4	8				Non Compliant	No Dome
PED1321	4	4	No	Yes	Good	16	0.5	10.2				Non Compliant	Running Slope
PED5789			Yes				0.7	4	Yes	1	1.6	Compliant	
PED451	5	4	Yes	Yes	Good	20	0.6	4.8	Yes	1.8	0.6	Compliant	
PED452	5.5	4	Yes	No	Good	22	0.3	4	Yes	1.3	0.4	Compliant	
PED454			Yes	No	Good	41.25	0.8	4.5	No			Compliant	
PED813	6.5	4	No	Yes	Good	26	1.1	3				Non Compliant	Running Slope
PED814	6.5	4.5	No	Yes	Good	29.25	1.7	6.6				Non Compliant	No Dome
PED815			No	No	Replace	1	0	0				Non Compliant	
PED816			No	No	Replace	1	0	0				Non Compliant	
PED817			No	No	Replace	1	0	0				Non Compliant	
PED818			No	No	Replace	1	0	0				Non Compliant	
PED819	4	4	No	No	Replace	16	0	0				Non Compliant	
PED1015	3	4	No	Yes	Good	12	0.2	7.6				Non Compliant	No Dome
PED1016	4	3	No	Yes	Fair	12	3.1	6.5				Non Compliant	Cross Slope
PED1017	3	3	No	Yes	Fair	9	2.6	9.1				Non Compliant	No Dome
PED1018	3	3	No	No	Fair	9	1.2	7.6				Non Compliant	No Dome
PED1019	3	3	No	Yes	Good	9	2.1	8.2				Non Compliant	Cross Slope
PED1020	3	3	No	Yes	Good	9	0	9.1				Non Compliant	Running Slope
PED1021	3	3	No	Yes	Fair	9	3.8	4.8				Non Compliant	Cross Slope
PED1022	4	3.5	No	Yes	Good	14	1.3	7.4				Non Compliant	No Dome
PED1023	4	3	No	Yes	Good	12	4.6	6.6				Non Compliant	Cross Slope
PED1024	3.5	3	No	Yes	Good	10.5	0.9	6.9				Non Compliant	No Dome
PED1648	6	6	Yes	No		32	1.9	3.6	No			Compliant	
PED1217	8	4	No	Yes	Good	32	0.6	5.8				Non Compliant	No Dome
PED1218	5	3	No	Yes	Replace	15	2.9	8.2				Non Compliant	Cross Slope
PED1219	5	4	No	Yes	Replace	20	0.7	5.9				Non Compliant	No Dome
PED1220	6	4	No	Yes	Replace	24	5.3	12.2				Non Compliant	No Dome
PED1221	6	4	No	Yes	Fair	24	1.2	11.5				Non Compliant	Running Slope
PED1222	5	5	No	Yes	Replace	25	2.8	10.3				Non Compliant	
PED1266	0	0	Yes	No	Good	0	0	0				Compliant	
PED1268	6	4	Yes	No	Replace	1	0	0				Non Compliant	
PED1269	6	4	Yes	No	Good	24	0.3	4.9	No			Compliant	
PED1270	6	4	Yes	No	Good	24	0.5	4.7	No			Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1667	10	10	Yes	No	Good	1	2.8	4.4	Yes	0.7	1.4	Compliant	Cross Slope
PED1266	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED337	9	2.5	No	No	Good	22.5	0.9	0.2				Non Compliant	No Dome
PED338	7	3	No	No	Good	21	0.7	9.1				Non Compliant	Running Slope
PED344	6	3	No	Yes	Good	18	0	1.1				Non Compliant	Running Slope
PED345	6	2	No	No	Fair	12	0.3	3.2				Non Compliant	Running Slope

City of Grand Rapids
 ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED1062	0	0	Yes	No	Good		2.5	3.6	No			Non Compliant	Cross Slope
PED73	0	0	Yes	Yes	Good		0.2	3.9	Yes	1.1	1.2	Compliant	
PED953	5	3	No	Yes	Good	15	3.2	4.6				Non Compliant	Cross Slope
PED954	6	4	No	Yes	Good	24	2	12.1				Non Compliant	Running Slope
PED955	6	4	No	Yes	Good	24	0.1	5.6				Non Compliant	No Dome
PED956	6	4	No	Yes	Good	24	1.7	3.6				Non Compliant	No Dome
PED957	6	4	No	Yes	Good	24	0.7	6.4				Non Compliant	No Dome
PED958	6	5	No	No	Replace	1	0	0				Non Compliant	Cross Slope
PED959	6	5	No	Yes	Good	30	6.9	5.4				Non Compliant	Running Slope
PED961	5	4	No	Yes	Good	20	0.5	9.4				Compliant	
PED1062	0	0	Yes	No	Good		0.7	1.1	No			Compliant	
PED1062	0	0	Yes	No	Good		2	2.2	No			Compliant	
PED73	6	6	Yes	Yes	Good	28	0.9	3.3	Yes	1.1	1.5	Compliant	
PED73	6	10	Yes	Yes	Good		1.3	3.9	Yes	0.2	1.4	Compliant	
PED73	6.5	10	Yes	Yes	Good		0.2	1.6	Yes	0.8	0.2	Compliant	
PED302	0	0	Yes	Yes	Good		0.9	3.3	Yes	0.9	0.7	Compliant	
PED315	6.5	6	Yes	Yes	Good	16.5	0.5	6.3	Yes	0.6	1.7	Compliant	
PED316	6	6	Yes	Yes	Good	15	0	0.3	No	0.8	1.6	Compliant	
PED317	6	6	Yes	Yes	Good	26	1.9	3.7	Yes	0.9	0.2	Compliant	
PED368	0	0	Yes	Yes	Good		0.5	4.2	Yes	0.3	0.7	Compliant	
PED368	0	0	Yes	Yes	Good		0.6	3.4	Yes	0.3	0.8	Compliant	
PED118	0	0	Yes	No	Good	0	0	0				Compliant	
PED118	0	0	Yes	No	Good	0	0	0				Compliant	
PED149	5	3	No	Yes	Good	15	0.4	4.7				Non Compliant	No Dome
PED150	8	4	No	Yes	Fair	32	0.7	1.3				Non Compliant	No Dome
PED152	6	5	Yes	Yes	Good	8	1.1	4.4	Yes	0.09	1.1	Compliant	
PED153	6.5	4	No	Yes	Good	26	4.1	4.4	Yes	1.2	0	Conditionally Compliant	
PED156	6.5	4	No	Yes	Good	26	1	8.7				Non Compliant	Cross Slope
PED368	0	0	Yes	Yes	Good		0.3	3.7	Yes	0.2	1	Compliant	Running Slope
PED368	0	0	Yes	Yes	Good		0.3	4.1	Yes	0.5	1	Compliant	
PED368	0	0	Yes	Yes	Good		0.6	3	Yes	1	0.3	Compliant	
PED368	0	0	Yes	Yes	Good		0.7	2.9	Yes	0.6	0.1	Compliant	
PED121	7	4	No	Yes	Good	28	0.6	2.7				Non Compliant	No Dome
PED122	7	4	No	No	Replace	1	0	0				Non Compliant	
PED123	5	3.5	No	Yes	Good	28	0.5	1.8				Non Compliant	No Dome
PED125	6	3	No	Yes	Good	18	0.5	7.6				Non Compliant	No Dome
PED126	6	3	No	Yes	Good	18	1.2	6				Non Compliant	No Dome
PED127	6	3	No	Yes	Good	18	0.8	8.4				Non Compliant	Running Slope
PED128	3.5	2	No	No	Good	7	2.3	12.9				Non Compliant	
PED130	8.5	5	Yes	Yes	Good	42.5	0	3.3				Compliant	
PED118	0	0	Yes	No	Good	0	0	0				Compliant	
PED118	0	0	Yes	No	Good	0	0	0				Compliant	
PED118	0	0	Yes	No	Good	0	0	0				Compliant	
PED710	6	7.5	Yes	Yes	Good		1	2.5	Yes	0.3	1.3	Compliant	
PED710	8.5	5	Yes	Yes	Good		0.9	1.3	Yes	0.1	1.6	Compliant	
PED710	6	6	Yes	Yes	Good	36	0.9	2.4	Yes	0.1	2.1	Compliant	
PED710	6.5	6	Yes	Yes	Good		1.5	2.2	Yes	1	0.2	Compliant	
PED710	0	0	Yes	Yes	Good		0.9	4.8				Compliant	
PED710	10	5	Yes	Yes	Good	26	0.8	2.7	Yes	0.6	0.3	Compliant	
PED710	10	5	Yes	Yes	Good		0.1	3.6	Yes	0.6	0.3	Compliant	
PED710	10	5	Yes	Yes	Good		1.8	4.3	Yes	0.3	0.8	Compliant	
PED710	10	5	Yes	Yes	Good		1.3	0.5	Yes	0.3	1.5	Compliant	
PED791	6	6	Yes	No	Good	0	1.4	3.7	Yes	1.4	0.1	Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	
PED1260	0	0	Yes	No	Good	0	0	0				Compliant	

City of Grand Rapids
 ADA Transition Plan - Pedestrian Curb Ramp Summary

Facility ID	Width (ft)	Length (ft)	Domes	Textured	Quality	Area (sf)	Cross Slope (%)	Running Slope (%)	Landing	Landing Cross Slope (%)	Landing Running Slope (%)	Compliance	Notes
PED228	6	5	Yes	Yes	Good		0.3	0.8	Yes	0.9	0.8	Compliant	
PED209	0	0	Yes	Yes	Good		0.2	1.9	Yes	0.4	1.3	Compliant	
PED210	0	0	No	No	Replace	1	0	0	Yes			Non Compliant	
PED211	6	6	Yes	Yes	Good	36	1.1	4.1	Yes	2	1.1	Compliant	
PED212	6	6	Yes	Yes	Good	36	0.6	6	Yes			Compliant	
PED213	6	6	Yes	Yes	Good	36	1	4.8	Yes	2.1	0.8	Non Compliant	Cross Slope
PED229	6	12	Yes	Yes	Good		0.4	1.5	Yes	1	0.5	Compliant	
PED230	6	11	Yes	Yes	Good		0.7	3.3	Yes	0	1.3	Compliant	
PED231	4	6	No	Yes	Good	24	0.5	8.5	Yes			Non Compliant	Running Slope
PED232	3	3.5	No	Yes	Replace	10.5	1.3	10.1				Non Compliant	Running Slope
PED239	5.5	5	Yes	No	Good	27.5	2	3.5	Yes	0.7	1.7	Non Compliant	Cross Slope
PED214	0	0	Yes	Yes	Good		0.9	3.9	Yes	0.2	1.5	Compliant	
PED215	6.5	6	Yes	Yes	Good	39	0.5	2.4	Yes			Compliant	
PED216	4	2	No	No	Fair	8	0.5	7.1				Non Compliant	No Dome
PED217	5	5.5	Yes	Yes	Good		0.6	2.5	No			Compliant	
PED702	6.5	7	Yes	Yes	Good		0.6	3.2	Yes	0	1.3	Compliant	
PED703	3	3.5	No	Yes	Fair	10.5	1.4	9.3				Non Compliant	Running Slope
PED704	3	3	No	Yes	Fair	9	0.4	7.5				Non Compliant	No Dome
PED705	5	4	No	Yes	Poor	20	1	5				Non Compliant	No Dome
PED706	6	2	No	No	Good	12	0.7	0.3				Non Compliant	No Dome
PED1325	0	0	Yes		Good		0.4	1.2	Yes	0.4	0.4	Compliant	
PED1326	0	0	Yes		Good		0.2	2.2	Yes	0.1	1.5	Compliant	
PED1331	11	5	No	Yes	Good	55	0.1	6				Non Compliant	No Dome
PED1189	5	5	Yes	No	Good	25	2.5	6.5	No			Non Compliant	Cross slope not compliant due to road slope
PED1223	8	4.5	No	Yes	Fair	36	1	10.7				Non Compliant	Running Slope
PED1224	5	3	No	Yes	Good	15	2.6	10.1				Non Compliant	
PED1227	15	4	Yes	No	Good	60	1.2	3.2	No			Compliant	
PED1228	15	5	Yes	No	Good	75	0.6	4.7				Compliant	
PED33			Yes	Yes	Good	22.5	0.7	2.8	Yes	0.6	0.1	Compliant	